

PETRA III
A High Brilliant
Synchrotron Radiation Source
in the Hard X-ray Regime

K. Balewski

for the PETRA III project team

DESY





Parameters of PETRA III

Design philosophy: cost effective (*)


and compatitive with high energy SR sources

Parameter	
# insertion devices (*)	13
energy (GeV)	6
max. current (mA)	>100
ϵ_x (nmrad)	1
ϵ_z (nmrad)	0.01




PETRA III

Conversion of PETRA II (2304 m circ.)






PETRA III New Experimental Hall





PETRA III

Low & High β_x Cell ($\beta_x=1.2\text{m}$ & $\beta_x=20\text{m}$)



4 * 5 m undulator
8 * 2 m undulator
12


ID properties		unit
λ	2.8	cm
B	0.9	T
cham. Height	7	mm
cham. Mat.	Al	

D_x small \rightarrow no sextupols here



PETRA III



long (20m) undulator in short straight



1



PETRA III optics of old octant





- 1) Phase advance per FODO cell 72° : compromise between small emittance and sufficiently large dynamic aperture
- 2) Chromaticity correction in old octants
- 3) Minimization of 1-st order sextupol effects
- 4) Alignment tolerances comparable to present status (1/4 mm)



PETRA III


damping wiggler

$\epsilon_x: 4 \rightarrow 1$ nmrad



Damping wigglers


- $B = 1.5$ T
- $\lambda = 0.2$ m
- $h = 0.025$ m
- $L_{\text{tot}} = 80$ m (2 x 40m)






PETRA III

dynamic aperture including perturbations





PETRA III Wiggler Section





PETRA III

Toushek Lifetime

Parameter	
total current (mA)	100
# bunches	40
current / bunch (mA)	2.5
momentum acc. (%)	1.5
Touschek lifetime (h)	2

PETRA III

Lifetime – Topping up

User demand 12 h run time → total lifetime \approx 24 h
→ Touschek lifetime \approx 50 h

Way out

- increase the number of bunches (960) → new feedback system
- Top up (time resolved measurements with a small number of bunches)
- More precise: injection at a Hertz rate (constants of $I_{\text{tot}} \approx 1 \text{ ‰}$)

Also attractive in case of many bunches

1. Fill appr. every minute (constants of $I_{\text{tot}} \approx 1 \text{ ‰}$)
2. → thermal equilibrium → relaxes burden of orbit stabilisation (SLS)

PETRA III

Orbit Stabilization

$\epsilon_x = 1\text{nmrad}$

coupling 1%

	Low β insertion			High β insertion		
	$\beta(\text{m})$	$\sigma(\mu\text{m})$	Amplification factor	$\beta(\text{m})$	$\sigma(\mu\text{m})$	Amplification factor
Horizontal	1.19	34.6	17.25	19.84	141	70.24
Vertical	4.0	6.3	34.08	2.37	4.9	26.20

Stab. Requirement $0.1 * \sigma$
→Sub micron orbit stability !!

PETRA III

Orbit Stabilization

Passive measures: improvement of magnet supports in old octants;
careful girder design etc.

Aktive measures: Fast orbit correction (up to 100 Hz)

Orbit measurement

- button monitors and appropriate electronics: seems to be o.k.

Layout of system still work in progress



PETRA III

current limitations

- **Multibunch instabilities are a problem:**
Present situation **PETRA II**

	longitudinal	horizontal	vertical
I_{thres} (mA)	7	6	6
$1/\tau$ (Hz)	35	50	60
Z_{eff}	3.6 M Ω	45 M Ω /m	54 M Ω /m

PETRA III: 12 instead of 16 cav. & larger long. (radiation) damping

→ powerful broadband ($BW \geq 60\text{MHz}$) feedback necessary



PETRA III hardware changes

new octant completely new hardware


Magnets

Vacuum system (stainless steel)


BPM

Valve


Corrector magnets




Quadrupole PQA



Quadrupole PQB




Quadrupole PQC





PETRA III preliminary girder design

side view



top view





PETRA III

hardware changes

- Old octant:
 - make use of existing hardware whenever possible
 - **To ensure reliable machine operation**
 - **New vacuum system**
 - Installation of more and new correctors and beam position monitors
 - Replace radiation damaged coils of magnets (experience!)
 - Modernize rf system
 - New coupled bunch feedback system
 - Diagnostics: wire scanner, parasitic bunch detection etc.



PETRA III dipole chamber old octant



Decoupling of vacuum chamber and quadrupoles
NEG pump because of small magnetic dipole field



PETRA III schedule

Schedule:

- completion of TDR end of 2003
- approval in the first half of 2004
- final design of comp. and ordering of hardware in 2005/2006
- rebuilding of PETRA in 2007
- start of commissioning of PETRA III and beam-lines in 2008
- start of routine operation in 2009